BUILT WITH CLAUDE, FILMED WITH HIGGSFIELD

# HOW TO BUILD A TOWER THAT SELLS WITH AI



## THE FULL BLUEPRINT

EVERY STEP AND EVERY PROMPT,
WORD FOR WORD

OMNYA LAB

START HERE

# WHAT YOU'LL HAVE AT THE END

- ✓ The photo of your tower before it is built, from a reference photo and one prompt.
- ✓ A site where the buyer picks the building, the floor and the apartment.
- ✓ The flight in through the glass and the walk from room to room, all real video.
- ✓ The way back to the tower in one move, with the logo at the end.
- ✓ One link for the developer, and it works on a phone.

## WHAT YOU NEED

**Claude Code**
It reads this PDF, writes the code and checks every step with you.

**Higgsfield, connected**
Turn on its connector in Claude so it can make the photos and the clips, or use the image and video tool you already have.

**ffmpeg**
To cut each clip on the exact frame, and Claude installs it for you.

**A free Vercel account**
To put the site online on a private link.

THE FAST WAY

# GIVE THIS PDF TO CLAUDE CODE

Open Claude Code in an empty folder, drop this PDF in it and paste the prompt below: Claude reads the PDF page by page, asks you a few questions about your tower and then builds it with you step by step, showing you the result every time before it moves on.

```
I bought the Full Tower Blueprint by Omnya Lab. The PDF is in this folder: read
it page by page, from chapter 00 to chapter 12, before you do anything.

I want to build what you see in the Omnya Lab tower video
(instagram.com/omnyalab): a tower that looks built, and a site where a buyer
picks a floor, flies in through the glass and walks through the apartment.

First ask me what you need to know about my tower: plans, number of floors,
heights, where it stands, which apartment to show. Then follow the PDF in order.
After every step show me the result (the 3D, the photo, the clip, the page in
the browser) and wait for my OK before the next one. Use Higgsfield through its
connector for every photo and every video. If something fails one of the checks
in the PDF, fix it before you go on.
```

The Full Tower Blueprint is the complete method behind SAMAR Residences, every file, every command and every line of code we use. Chapter 00 gives you the tower photo with every prompt, word for word. From chapter 01 on you have the tower, and now you want a buyer to choose a building, a floor and an apartment, and to see that apartment from the inside before a single slab is poured. You will build it the way we built SAMAR, with real video, an SVG layer traced on the first frame and about three hundred lines of plain JavaScript. No game engine, no plugin, nothing to install on the buyer's phone.

You need the tower images from chapter 00, an account on Higgsfield (Seedance and Kling), ffmpeg, a code editor and a free Vercel account. Claude Code can write and fix most of the code with you, and we tell you where it helps the most.

CHAPTER 00

# THE TOWER PHOTO

## EVERY PROMPT, WORD FOR WORD

SAMAR did not start from a 3D. It started from a photo of the tower we already had and a second photo used only for the camera, on Nano Banana Pro in Higgsfield, 16:9, 2K. It took four prompts. These are all of them, in the order we wrote them, with what happened to each one.

### FIRST TRY: NO REFERENCE

A description of a tower with no picture of it. The model made its own building and it was not ours: rejected at once.

**PROMPT A · NANO BANANA PRO · REJECTED**

```
Ultra-realistic architectural photograph of a slender luxury residential tower in
Dubai Marina at blue hour, just after sunset. 16:9 wide frame, camera at drone
height (about 60 m), looking slightly up, eye level with the lower third of the
tower.

The tower: around 30 floors, tall and slim, a softly twisting oval plan. Every
floor has a continuous curved balcony slab in warm white concrete that wraps
around the building like a ribbon, the slabs gently shifting from floor to floor
so the silhouette breathes. Floor-to-ceiling glass behind each slab, frameless
glass balustrades. About a third of the apartments have warm 2700K interior lights
on, scattered naturally across floors, never in a pattern. The crown is clean and
flat, no spire, no logo.

Composition: the tower stands just left of center and fills the full frame height,
top almost touching the upper edge. The right 40% of the frame is open sky,
completely clean, for a UI panel.

Base: a low, elegant two-storey podium with a colonnade, warmly lit from below, a
short lit palm-lined driveway. In the foreground, the marina: rows of white yachts
moored in calm dark water with soft reflections of the warm lights, a promenade
with tall palms and low garden lights, a hint of beach and the Gulf on the right
towards the horizon.

Sky: smooth clean gradient from deep cyan blue at the top to soft peach and pale
orange at the horizon, no clouds, no sun, no stars. The water and glass reflect
this gradient.

Photography: Phase One medium format, 32mm tilt-shift lens, verticals perfectly
straight, f/8, everything sharp from foreground yachts to the tower crown, long
exposure feel so the water is glassy. Real architectural photography in the style
of a luxury developer launch, natural contrast, true colours, no HDR look.

Avoid: people, cars, text, logos, signage, lens flare, bloom, heavy vignette,
fisheye distortion, cartoon or CGI look, oversaturated colours, repeated identical
windows, other tall towers competing in the frame.
```

## TWO REFERENCES, ONE JOB EACH

Reference 1 is the photo of the building, reference 2 is a photo taken from the height we wanted. The first line of the prompt says which one is for what, so the second picture never changes the tower.

**PROMPT C · NANO BANANA PRO · REFERENCE 1 THE BUILDING, REFERENCE 2 THE CAMERA**

```
Use reference 1 for the building: keep this exact tower design identical — white
wavy cantilevered floor slabs offset floor by floor, flat thin cantilevered roof
canopy, clear floor-to-ceiling glass, about 17 floors, same proportions. Use
reference 2 only for camera position and depth, not for the building.

Elevated three-quarter aerial view, 16:9, camera about 80 m high and 300 m away,
looking slightly down. The tower stands just left of center on the Dubai Marina
waterfront and rises to about 80% of the frame height. Below it: the marina basin
with rows of white yachts and calm water, palm-lined promenades, low warm garden
lights. Behind it: the calm Gulf and a long horizon; on the left, far in the
distance, the Dubai Marina skyline softly hazed. The right 40% of the frame is
open, clean sky.

Light: blue hour, ten minutes after sunset. Sky gradient from deep cyan at the top
to soft peach at the horizon. Warm 2700K lights on inside about a third of the
apartments, scattered randomly, so the slabs glow from within; podium and
colonnade warmly lit.

Shot on DJI Inspire 3, 24mm, f/5.6, everything sharp, light atmospheric haze on
the horizon for depth, natural contrast, true colours, real luxury developer
launch photography.

Avoid: changing the tower design, extra floors, eye-level or frontal symmetric
view, people, cars, text, logos, lens flare, HDR, oversaturation, CGI look.
```

The building came back right, the camera came back right, and the tower was too short: 17 floors looked like a hotel.

## THE ONE WE KEPT

The same prompt with the height fixed in three places: in the building line, in the framing and in what to avoid, plus one last line that says it again.

**PROMPT D · NANO BANANA PRO · APPROVED**

```
Use reference 1 for the building: keep this exact tower design — white wavy
cantilevered floor slabs offset floor by floor, flat thin cantilevered roof
canopy, clear floor-to-ceiling glass — same slab design and roof, but taller: 25
floors, slender proportions, height about 4 times its width. Use reference 2 only
for camera position and depth, not for the building.

Elevated three-quarter aerial view, 16:9, camera about 80 m high and 300 m away,
looking slightly down. The tower stands just left of center on the Dubai Marina
waterfront and rises to about 85% of the frame height, roof just below the top
```

```
edge. Below it: the marina basin with rows of white yachts and calm water, palm-
lined promenades, low warm garden lights. Behind it: the calm Gulf and a long
horizon; on the left, far in the distance, the Dubai Marina skyline softly hazed.
The right 40% of the frame is open, clean sky.

Light: blue hour, ten minutes after sunset. Sky gradient from deep cyan at the top
to soft peach at the horizon. Warm 2700K lights on inside about a third of the
apartments, scattered randomly, so the slabs glow from within; podium and
colonnade warmly lit.

Shot on DJI Inspire 3, 24mm, f/5.6, everything sharp, light atmospheric haze on
the horizon for depth, natural contrast, true colours, real luxury developer
launch photography.

Avoid: changing the tower design, fewer than 25 floors, eye-level or frontal
symmetric view, people, cars, text, logos, lens flare, HDR, oversaturation, CGI
look.

25 floors, noticeably taller than the reference.
```

This is the photo on the cover, upscaled once at the end. It is also the first frame of the flight in chapter 03, so every floor you trace in chapter 05 sits on this exact picture.

### WHAT CHANGED FROM C TO D

- The floors: “about 17 floors, same proportions” became “25 floors, slender proportions, height about 4 times its width”.
- The framing: “about 80% of the frame height” became “about 85%, roof just below the top edge”.
- What to avoid: “extra floors” became “fewer than 25 floors”.
- A last line repeating the height, because the model listens most to the start and the end.

### THE END FRAME: THE LIVING ROOM FROM THE TERRACE

Before any video, make the picture where the flight lands. Four references, uploaded in this order: 1 the approved tower, 2 a Minotti photo for the sofa and the dark wood, 3 a Lindsey Adelman chandelier, 4 a sample of Noce travertine. The first two rounds were rejected (a lighter sofa, objects on the table, a front view). The third moved the camera to a 45 degree angle and opened a door onto the bathroom; we changed only those two passages of the second round, and this is the full text that came out:

**LIVING ROOM FROM THE TERRACE · NANO BANANA PRO · APPROVED**

```
Image 1 is the tower: this living room is on the 14th floor of this exact
building; the thick white curved balcony slab of Image 1 runs across the top of
the frame. Image 2 is the sofa and the wood panelling: use this exact sectional
sofa shape and this dark wood. Image 3 is the chandelier: use this exact light
installation over the seating. Image 4 is the stone for the TV wall.
```

Interior photograph of the living room of a sky residence in Dubai Marina at blue hour, ten minutes after sunset, seen from the terrace. The camera stands on the terrace at the corner of the building, at 1.5 m height, at a sharp 45 degree angle to the façade: the open glass wall runs diagonally across the frame from the left foreground deep into the right background, so the room is seen from its corner and never from the front. The fully open sliding glass panels are stacked at the near left edge, their dark bronze frames close to the lens and out of focus. 24mm lens, verticals perfectly straight. Across the top of the frame the thick white curved underside of the balcony slab above. On the far right, beyond the terrace, the deep blue Gulf and a peach horizon.

Terrace floor: large-format honed Travertino Silver, unfilled, pale grey, with soft reflections of the interior lights; the same stone continues into the room at the same level.
Back wall: book-matched walnut-brown Noce travertine slabs floor to ceiling from Image 4, honed, open pores, with a large black TV recessed flush in the stone and a long low floating cabinet in fumed oak, deep honey-brown, below it.
Left wall: fumed oak panelling with thin bronze reveals, deep honey-brown, like Image 2.
Ceiling: a ceiling of fumed oak slats between dark plaster beams, 3.2 m high, one single recessed warm light line along the glass edge only; a narrow band of ceiling at the top of the room.
Second room: at the far right end of the room a tall pivot door in fumed oak stands wide open, and through it the primary bathroom is clearly visible and warmly lit: walls of book-matched honed Fior di Pesco Carnico, plum-grey marble with white veins, a sculptural freestanding bathtub carved from a single block of Travertino Silver in front of a floor-to-ceiling window onto the blue Gulf, a recessed warm light washing the stone wall.
Curtains: full-height sheer curtains in smoke-grey silk organza gathered at the right edge of the opening.
Sofa: a long low sectional sofa shaped like Image 2, about 360 cm, upholstered in deep graphite grey wool felt, dark and rich, with cushions in charcoal heavy linen and one cushion in cognac leather.
Armchairs: a pair of armchairs like Minotti Daiki, dark burnished wood frame, seats in black suede, facing the sofa.
Coffee table: a low rectangular coffee table 160 x 90 cm, a solid top of honed Rosso Levanto, deep red serpentinite with white and green veins, thin blackened steel frame; its stone top is completely empty and clean, only the veined red stone visible.
Rug: a large hand-knotted rug in deep espresso wool and silk with a large tonal pattern of curved bands in espresso and bronze.
Chandelier: the installation from Image 3 hangs low over the coffee table, its glass glowing warm.
Lamp: a Flos Captain Flint floor lamp in dark bronze at the end of the sofa, lit, its cable running to the wall.
Art: one large unsigned work of burnt wood and black canvas in the spirit of Burri, black and dark brown, hung at eye level on the oak wall, thin bronze frame.
Object: one large sculptural vessel in black clay on the floating cabinet, the only object in the room.
Light: warm 2700K interior light, interior brighter than the sky, cool blue light from the sky on the terrace.

```
Editorial architecture photograph in the spirit of Simon Upton, natural colour
like a Kodak Portra 400 film scan, gentle highlight roll-off, fine film grain,
deep shadows.
```

### CHECK IT BEFORE YOU GO ON

If one check fails, don’t edit the picture: write the whole prompt again with the fix inside, as we did from C to D. Upscale only the image you keep.

- The number of floors you wrote, counted one by one.
- Vertical lines straight, the tower not leaning back.
- Balconies that line up floor after floor, with no melted slabs.
- Not every window lit, and no invented logos or text.
- The end frame in the same light as the tower: the same blue hour, the same sky.

CHAPTER 01

# WHAT YOU ARE BUILDING

## AND WHY IT SELLS

A developer selling off plan has floor plans, a price list and a few renders. The buyer still has to imagine which floor is theirs and what they see from it. The experience answers that in under a minute, in this order:

1. **The site:** One or more towers seen from far away. The buyer clicks a building.
2. **The floor:** Moving over the tower lights up one floor at a time, with its number. A glass panel shows level, unit type, area and view.
3. **The apartment:** The buyer picks an apartment on the floor plan of that level, or goes straight in.
4. **The flight:** The camera flies from the tower to the terrace of that floor, through the glass and into the living room.
5. **The rooms:** Pills on the video lead to the next room (living room, then bathroom or bedroom).
6. **The return:** "Back to the tower" plays the whole way back in one move, and the project logo builds up on the last stretch.
7. **The action:** "Register interest" stays on screen the whole time.

Everything you see on screen is video. The only thing drawn by code is the light on the floors, the panel and the pills. That is why it looks like a film and still loads on a phone.

CHAPTER 02

# THE SHOT LIST

## BEFORE YOU GENERATE ANYTHING

Write the whole path on paper first. Every arrow in the experience is one clip, and every clip has to start on the exact last frame of the one before. For one tower with one showcase apartment the list is short:

| CLIP | FROM | TO | TOOL |
|---|---|---|---|
| fly | the tower, far away | the terrace, then the living room | Seedance, start and end frame |
| enter | last frame of fly | inside the living room | Kling, start frame |
| bath | last frame of enter | the bathroom | Kling, start frame |
| back-* | any room | the tower | no generation: the same frames in reverse |

Two rules decide whether the result looks real. All clips are exactly 1920 × 1080 at 24 frames per second, so they swap without a jump. And the tower frame you trace the floors on is the first frame of the flight, never a separate still, so the floors line up with the video to the pixel.

> One showcase apartment is enough to sell the whole tower. Buyers choose a floor for the view and the height; the interior shows the finish level. If the developer wants each unit type inside, repeat chapter 03 once per type and share the tower and the flight.

CHAPTER 03

# THE CLIPS

## ONE START FRAME AT A TIME

### THE FLIGHT

On Seedance, the tower photo is the start frame and the living room from the terrace is the end frame. Make a 480p draft first: it is cheap and tells you if the move works. This was the first prompt:

**SEEDANCE · FIRST VERSION**

```
One single continuous drone shot, no cuts. The camera starts exactly on the first
frame: the white tower on the Dubai Marina waterfront at blue hour. It flies
forward and slightly upward towards the tower, smoothly accelerating, heading for
the 14th floor, the floor just above the middle of the building. As it approaches,
the white curved balcony slabs grow larger and pass above the lens, the warm lit
windows of the 14th floor fill the frame. The camera slows down, glides over the
terrace of the 14th floor, under the curved white slab of the floor above, and
comes to rest in front of the fully open sliding glass wall, looking into the
warmly lit living room, matching the last frame exactly.

Steady gimbal movement, constant forward motion, no rotation, no shaking. The
building, the balconies and the room stay exactly the same as in the two frames.
Blue hour light constant throughout, warm interior lights, calm sea.
```

The draft came out well, the 1080p take did not: it removed a column and dissolved into the room instead of flying in. So we added this paragraph:

**SEEDANCE · THE PARAGRAPH WE ADDED**

```
The camera physically flies through the open sliding glass wall, the facade,
columns and glass stay solid and in place for the whole shot, the balcony slab
stays above the camera at all times, the transition is a real camera movement, not
a dissolve.
```

And this is the full prompt we ran again. The clip we use is 1080p, 5 seconds, 24 frames per second.

**SEEDANCE · SECOND VERSION**

```
One single continuous drone shot, no cuts, no dissolves. The first second holds
the first frame exactly, then the camera starts moving slowly: the white tower on
the Dubai Marina waterfront at blue hour. The camera flies forward and slightly
upward towards the tower, smoothly accelerating, heading for one floor slightly
above the middle of the building. As it approaches, the white curved balcony slabs
grow larger and pass above the lens, the warm lit windows of that floor fill the
frame. The camera slows down, glides over the terrace of that floor, under the
curved white slab of the floor above, and comes to rest in front of the fully open
sliding glass wall, looking into the warmly lit living room, matching the last
```

```
frame exactly.

The camera physically flies through the space; the facade, columns and glass stay
solid and in place for the whole shot, the balcony slab stays above the camera at
all times, the transition is a real camera movement, not a dissolve.

Steady gimbal movement, constant forward motion, no rotation, no shaking. The
building, the balconies and the room stay exactly the same as in the two frames.
Blue hour light constant throughout, warm interior lights, calm sea.
```

### EXTRACT THE REAL LAST FRAME

Each next clip starts from the last frame of the one you keep. Be careful: `-sseof -0.04` in ffmpeg often gives you the second to last frame, and that tiny jump is what makes a cut visible. Count the frames and take the last one by number:

```
ffprobe -v error -count_frames -select_streams v:0 \
  -show_entries stream=nb_read_frames -of csv=p=0 fly.mp4
# say it prints 120: the last frame is number 119
ffmpeg -i fly.mp4 -vf "select='eq(n\,119)'" -vframes 1 fly_last.png
```

On SAMAR we cut the flight at frame 119 because that is where the living room is fully in view. Pick your own cut point, then extract that exact frame.

### THE ROOMS

On Kling, with a start frame and an end frame, one slow move per clip. From the terrace into the living room:

**KLING · TERRACE TO LIVING ROOM**

```
Smooth continuous dolly shot. The camera glides slowly forward from the terrace
through the fully open sliding glass wall into the living room, at eye level,
passing beside the grey sofa, and gently turns right to face the travertine wall
with the TV, ending on the last frame. Slow, steady, gimbal-stabilised movement.
Warm interior lights, blue hour outside.
```

From the living room to the bathroom:

**KLING · LIVING ROOM TO BATHROOM**

```
Smooth continuous dolly shot. The camera moves slowly forward across the living
room towards the open oak door on the right, passes through the doorway into the
bathroom, and gently turns left to reveal the stone vanity and the travertine
bathtub by the window, ending on the last frame. Slow, steady, gimbal-stabilised
movement. Warm interior lights, blue hour outside the windows.
```

The same negative prompt for both:

**KLING · NEGATIVE PROMPT**

```
cuts, fade, morphing, warping furniture, objects appearing or disappearing,
people, camera shake, fast movement, flicker, distorted walls
```

The first bathroom take showed the bathtub twice, once through the door and once inside. This is the fix we wrote, with its own negative prompt:

**KLING · LIVING ROOM TO BATHROOM, ONE BATHTUB**

```
Smooth continuous dolly shot. The camera moves slowly forward across the living
room straight towards the open oak door on the right, keeping the bathtub visible
through the doorway in view the whole time. There is only one bathtub: the oval
travertine bathtub seen through the door is the same one at the end. The camera
passes through the doorway and the bathtub grows larger and slides to the lower
right of the frame, next to the window, while the camera gently turns left to
reveal the stone vanity and mirror, ending exactly on the last frame. The bathtub
never leaves the frame and never changes. Slow, steady, gimbal-stabilised
movement. Warm interior lights, blue hour outside the windows.
```

**KLING · NEGATIVE PROMPT, ONE BATHTUB**

```
second bathtub, duplicate bathtub, new objects appearing, cuts, fade, morphing,
warping furniture, people, camera shake, fast movement, flicker, distorted walls
```

For the takes on the site we started again from the real last frames: the living room clip from frame 119 of the flight, with the terrace-to-living-room prompt above, and the bathroom clip from the last frame of that living room clip. The text of that last bathroom prompt was not saved; start from the one-bathtub fix above.

## MATCH THE COLOUR

Two generators never give you the same colour. Our bathroom came out colder than the living room, so we made a LUT once, matching it to the previous clip, and baked it in:

```
ffmpeg -i bath_raw.mp4 -vf "lut3d=file=bath_match.cube,scale=1920:1080" \
  -c:v libx264 -preset slow -crf 10 -pix_fmt yuv420p -movflags +faststart
bath.mp4
```

> What not to do, because we tried it: optical-flow interpolation between clips, crossfades, motion blur on the joins, stills between two videos. All of them look cheap next to the original footage. Keep only real frames.

CHAPTER 04

# THE WAY BACK

## WITHOUT GENERATING ANYTHING

The return to the tower is the same footage played backwards, joined into one clip per room, so the camera never stops on the way out. From the bathroom it is: bathroom reversed, then living room reversed, then flight reversed.

```
# from the terrace: flight frames 0..119, reversed
ffmpeg -i fly.mp4 -filter_complex \
 "[0:v]select='lte(n\,119)',setpts=N/24/TB,reverse[o]" -map "[o]" \
 -c:v libx264 -preset slow -crf 10 -pix_fmt yuv420p -movflags +faststart back-
terrace.mp4

# from the bathroom: three clips reversed and joined, the shared frames kept
once
ffmpeg -i fly.mp4 -i enter.mp4 -i bath.mp4 -filter_complex \
 "[2:v]setpts=N/24/TB,reverse[b];\
  [1:v]select='lte(n\,95)',setpts=N/24/TB,reverse[l];\
  [0:v]select='lte(n\,118)',setpts=N/24/TB,reverse[f];\
  [b][l][f]concat=n=3:v=1:a=0[o]" -map "[o]" \
 -c:v libx264 -preset slow -crf 10 -pix_fmt yuv420p -movflags +faststart back-
bath.mp4
```

Notice `lte(n\,118)` in the last line: frame 119 is already the first frame of the living room clip, so we keep it once. If you keep it twice the camera stutters on the join.

### EVEN OUT THE SPEED

AI clips slow down at the start and at the end. Reversed and joined, those slow stretches become little stops. This script measures how much each frame moves and chooses which original frames to show, so the camera keeps one speed and eases in on the tower. It makes no new pixels.

```
# even_return.py  src.mp4  out.mp4  seconds      (pip install numpy opencv-
python)
import sys, subprocess, numpy as np, cv2
src, out, dur = sys.argv[1], sys.argv[2], float(sys.argv[3]); FPS = 24
cap = cv2.VideoCapture(src); small = []
while True:
    ok, f = cap.read()
    if not ok: break
    small.append(cv2.resize(cv2.cvtColor(f, cv2.COLOR_BGR2GRAY), (320,
180)).astype(np.float32))
d = np.array([np.abs(small[i] - small[i-1]).mean() for i in range(1,
len(small))])
d = np.maximum(d, 0.05 * np.median(d))
C = np.concatenate([[0], np.cumsum(d)]); C /= C[-1]
ease = lambda t: t * t * (3 - 2 * t)
n = int(round(dur * FPS))
pick = [int(np.clip(np.searchsorted(C, ease(k / (n - 1))), 0, len(small) - 1))
for k in range(n)]
p = subprocess.Popen(['ffmpeg','-v','error','-y','-f','rawvideo','-
pix_fmt','bgr24','-s','1920x1080',
  '-r',str(FPS),'-i','-','-c:v','libx264','-preset','slow','-crf','10','-
pix_fmt','yuv420p',
  '-movflags','+faststart',out], stdin=subprocess.PIPE)
cap = cv2.VideoCapture(src); i = -1; frame = None
for k in pick:
    while i < k:
        ok, frame = cap.read(); i += 1
    p.stdin.write(frame.tobytes())
p.stdin.close(); p.wait()
```

Run it on each `back-*.mp4` and try a few durations. The right one is the shortest where nothing jumps.

CHAPTER 05

# TRACING THE FLOORS

## ON THE FIRST FRAME

Export frame 0 of `fly.mp4` as a PNG. Every floor becomes one closed shape on that image, in its own pixel space (0 to 1920, 0 to 1080). There are three ways to get the shapes, from fastest to most precise:

1. **By hand in Figma or Illustrator:** Put the PNG on a 1920 × 1080 artboard, draw one polygon per floor band, export as SVG and copy the `d` of each path.
2. **From the slab lines:** If your tower has visible slab edges, trace only the top and bottom edge of the facade as two polylines and split the height evenly into floors. This is what we did on SAMAR: points every 6 pixels along each slab edge, so the band follows the curve of the facade.
3. **From the 3D model:** If you still have the block model with the same camera, render one mask per floor (each floor a flat white material, everything else black) and let Claude Code turn the masks into paths with OpenCV `findContours`.

Store each floor as data, bottom to top. The numbers are the ones the sales team gives you:

```
const floors = [
  { n: 1,  d: "M566 767.9 L572 768.8 ... Z", xr: 878, mid: 790,
    unit: "Two bedrooms", area: 142, out: "Marina view" },
  // ...
  { n: 15, d: "M... Z", xr: 902, mid: 512,
    unit: "Three bedrooms + study", area: 238, out: "Sea and marina" },
];
```

`xr` is the right edge of the band and `mid` its vertical centre: the floor number sits there, on a short line, outside the tower.

### DRAW THEM OVER THE VIDEO

The trick that keeps the floors on the tower at every screen size is to give the SVG the same box and the same crop as the video: `viewBox="0 0 1920 1080"` with `preserveAspectRatio="xMidYMid slice"` is exactly what `object-fit: cover` does to the video.

```
<video class="clip on" id="v-fly" muted playsinline preload="auto"></video>
<svg class="floors" id="floors" viewBox="0 0 1920 1080"
preserveAspectRatio="xMidYMid slice">
  <defs>
    <filter id="soft"><feGaussianBlur stdDeviation="7"/></filter>
    <linearGradient id="fade" x1="0" x2="1">
      <stop offset="0" stop-color="#ffbf55" stop-opacity="0"/>
      <stop offset=".5" stop-color="#ffcf8a" stop-opacity=".9"/>
      <stop offset="1" stop-color="#ffbf55" stop-opacity="0"/>
    </linearGradient>
  </defs>
</svg>
```

```
.clip { position:absolute; inset:0; width:100%; height:100%; object-fit:cover;
opacity:0; }
.clip.on { opacity:1; }
svg.floors { position:absolute; inset:0; width:100%; height:100%; }
.floor path.hit { fill: transparent; cursor: pointer; }
.floor path.shape { fill:url(#fade); opacity:0; mix-blend-mode:screen;
filter:url(#soft);
                    transition: opacity .3s; pointer-events:none; }
.floor.hover path.shape { opacity:.9; }
.floor line, .floor text { opacity:0; transition: opacity .25s; pointer-
events:none; }
.floor.hover line, .floor.hover text { opacity:1; }
```

The warm light is a blurred gradient in screen blend mode, so it reads as light coming from inside the glass and not as a coloured sticker. Each floor gets two copies of the same path: an invisible one that catches the mouse and the visible one that glows.

CHAPTER 06

# THE FLOOR PICKER

## PANEL, HOVER AND CLICK

```
<aside class="panel glass" id="panel">
  <h1>Choose<br>your floor</h1>
  <div class="level"><small>Level</small><span class="num" id="num">15</span>
</div>
  <div class="unit" id="unit"></div>
  <div class="meta" id="meta"></div>
  <button class="enter pill btn-blue" id="enter">Enter level 15</button>
</aside>
```

```
const NS = 'http://www.w3.org/2000/svg', svg =
document.getElementById('floors');
const $ = id => document.getElementById(id);
let current = null;

floors.forEach(f => {
  const g = document.createElementNS(NS, 'g'); g.setAttribute('class',
'floor');
  g.innerHTML = `<path class="hit" d="${f.d}"/><path class="shape"
d="${f.d}"/>
    <line x1="${f.xr+26}" x2="${f.xr+76}" y1="${f.mid}" y2="${f.mid}"/>
    <text x="${f.xr+88}" y="${f.mid+8}">${f.n}</text>`;
  g.addEventListener('mouseenter', () => pick(f, g));
  g.addEventListener('click', () => { pick(f, g); fly(); });
  f.el = g; svg.appendChild(g);
});

function pick(f) {
  floors.forEach(x => x.el.classList.toggle('hover', x === f));
  if (f === current) return;
  current = f;
  gsap.fromTo('#num', { yPercent: 30, opacity: 0 }, { yPercent: 0, opacity: 1,
duration: .35, ease: 'power2.out' });
  $('num').textContent = f.n;
  $('unit').textContent = f.unit;
  $('meta').textContent = `${f.area} m² · ${f.out}`;
  $('enter').textContent = `Enter level ${f.n}`;
}
pick(floors[14]);   // open on the showcase floor
```

### THE GLASS

Clear glass with a heavy blur and a thin bright rim, no coloured fill. Solid blue for the one action that goes forward, white for everything else.

```
.glass { background: rgba(255,255,255,.10);
  backdrop-filter: blur(28px) saturate(180%); -webkit-backdrop-filter:
blur(28px) saturate(180%);
  box-shadow: inset 0 0 0 .5px rgba(255,255,255,.45), inset 0 1px 1px
rgba(255,255,255,.35),
              0 8px 30px rgba(0,0,0,.18); }
.btn-blue  { background:#0a84ff; color:#fff; }
.btn-white { background:#fff; color:#1d1d1f; }
.pill { height:40px; padding:0 18px; border-radius:999px; font-weight:600; }
```

Use GSAP from cdnjs for the few animations ( `gsap@3.12.5` ). Every floor stays selectable, even the ones you have no interior for: the flight is the same, and the panel is what changes.

CHAPTER 07

# THE BUILDING AND THE APARTMENT

## TWO MORE LAYERS ON THE SAME IDEA

### MORE THAN ONE BUILDING

A masterplan with several towers works exactly like the floors, one level up. Generate one wide aerial image of the whole site, trace one shape per building, and on click play a short Seedance move from the aerial to that tower's first frame (start frame = aerial, end frame = frame 0 of that tower's `fly.mp4`). Then the floor picker of chapter 06 opens on that tower.

```
const buildings = [
  { id: 'a', name: 'Tower A', d: 'M... Z', intro: 'assets/site-to-a.mp4',
floors: floorsA },
  { id: 'b', name: 'Tower B', d: 'M... Z', intro: 'assets/site-to-b.mp4',
floors: floorsB },
];
```

### THE APARTMENT ON THE FLOOR

When a floor has more than one unit, the buyer picks the unit on the plan of that level before flying in. Clean the architect's plan into a flat drawing (white walls on a dark background works well over video), and draw one shape per unit in the same way you drew the floors, this time in the plan's own pixel space.

```
const units = {
  15: [
    { id: '15A', d: 'M120 80 L540 80 L540 420 L120 420 Z', type: 'Three
bedrooms + study',
      area: 238, status: 'available', interior: 'type-3b' },
    { id: '15B', d: 'M540 80 L900 80 L900 420 L540 420 Z', type: 'Two
bedrooms',
      area: 164, status: 'reserved', interior: 'type-2b' },
  ],
};

function showPlan(level) {
  const list = units[level.n];
  if (!list) return fly();                          // one unit per floor: go
straight in
  plan.innerHTML = list.map(u =>
    `<path class="unit ${u.status}" data-id="${u.id}" d="${u.d}"/>`).join('');
  plan.querySelectorAll('.unit.available').forEach(p =>
    p.addEventListener('click', () => { chosen = list.find(u => u.id ===
p.dataset.id); fly(); }));
  gsap.to('#planbox', { opacity: 1, duration: .4 });
}
```

Reserved and sold units stay on the plan in grey and are not clickable: the buyer sees that the building is selling. `interior` says which set of room clips to play, so ten units of the same type share one set of videos.

> Keep the availability in one JSON file (`units.json`) that the sales team can edit. The page reads it on load, so marking a unit as sold never needs a new deploy of the code.

CHAPTER 08

# THE PLAYER

## SO NOTHING STALLS

One `<video>` element per clip, stacked, all muted and `playsinline`. Each file is downloaded whole into memory before the experience starts, because a video that buffers halfway through a flight breaks the illusion at once.

```
const CLIPS = { fly: 'assets/fly.mp4', enter: 'assets/enter.mp4', bath:
'assets/bath.mp4',
  'back-terrace': 'assets/back-terrace.mp4', 'back-living': 'assets/back-
living.mp4',
  'back-bath': 'assets/back-bath.mp4' };
let ready = 0; const total = Object.keys(CLIPS).length;
Object.entries(CLIPS).forEach(async ([id, src]) => {
  const blob = await (await fetch(src)).blob();
  const v = $('v-' + id);
  v.src = URL.createObjectURL(blob);
  v.addEventListener('loadeddata', () => {
    ready++; $('loader').textContent = `Loading ${Math.round(ready / total *
100)}%`;
    if (ready === total) gsap.to('#loader', { opacity: 0 });
  }, { once: true });
  v.load();
});
```

Swapping clips is a show then hide, two animation frames apart, so there is never a black frame between them:

```
let showing = $('v-fly');
function swapTo(el) {
  el.classList.add('on');
  if (showing && showing !== el) {
    const old = showing;
    requestAnimationFrame(() => requestAnimationFrame(() =>
old.classList.remove('on')));
  }
  showing = el;
}
function play(id, onStart) {
  const v = $('v-' + id);
  return new Promise(resolve => {
    v.pause(); v.currentTime = 0;
    const start = () => { swapTo(v); v.play(); onStart && onStart(v);
      v.addEventListener('ended', resolve, { once: true }); };
    if (v.readyState >= 2 && !v.seeking) start(); else
v.addEventListener('seeked', start, { once: true });
  });
}
```

### WEIGHT

We encode at `-crf 10` because the master has to survive a 21:9 monitor. For the public page make a second set at `-crf 20` and a 1280 × 720 set for phones, and choose by screen width before the fetch. Test the total on a real 4G connection: the loader must reach 100 % in a few seconds.

CHAPTER 09

# ROOMS AND HOTSPOTS

## A SMALL STATE MACHINE

Room pills sit on the footage at a fixed point of the frame ( `data-u` , `data-v` from 0 to 1). This function moves them with the video's crop at any window size:

```
function placeSpots() {
  const iw = 1920, ih = 1080, s = Math.max(innerWidth / iw, innerHeight / ih);
  const ox = (innerWidth - iw * s) / 2, oy = (innerHeight - ih * s) / 2;
  document.querySelectorAll('.spot').forEach(el => {
    el.style.left = (ox + el.dataset.u * iw * s) + 'px';
    el.style.top  = (oy + el.dataset.v * ih * s) + 'px';
  });
}
placeSpots(); addEventListener('resize', placeSpots);
```

The experience is always in one state, and one flag blocks double clicks while a clip plays. This is the whole logic:

```
let state = 'tower', busy = false;
async function fly() {
  if (busy || state !== 'tower' || ready < total) return;
  busy = true;
  gsap.to(['#panel', '#floors'], { opacity: 0, duration: .4 });
  $('back').classList.add('on');
  document.querySelectorAll('.lvl').forEach(el => el.textContent = `Level
${current.n}`);
  await play('fly');
  state = 'terrace'; busy = false; captions('cap-terrace'); $('spot-
in').classList.add('on');
}
$('spot-in').addEventListener('click', async () => {
  if (busy || state !== 'terrace') return;
  busy = true; captions(); await play('enter');
  state = 'living'; busy = false; captions('cap-living'); $('spot-
bath').classList.add('on');
});
$('spot-bath').addEventListener('click', async () => {
  if (busy || state !== 'living') return;
  busy = true; captions(); await play('bath');
  state = 'bath'; busy = false; captions('cap-bath');
});
```

The caption in the corner says where you are ("Level 15 · Living Room") and changes only when the camera has stopped.

CHAPTER 10

# THE RETURN AND THE ENDING

## THE MOMENT PEOPLE REMEMBER

```
$('back').addEventListener('click', async () => {
  if (busy || !['terrace', 'living', 'bath'].includes(state)) return;
  busy = true; captions();
  const id = { terrace: 'back-terrace', living: 'back-living', bath: 'back-
bath' }[state];
  await play(id, v => { const lead = v.duration * .55;
    gsap.delayedCall(v.duration - lead, () => finale(lead)); });
  state = 'end'; busy = false; $('back').classList.remove('on');
$('restart').classList.add('on');
});
function finale(dur) {
  return gsap.timeline()
    .fromTo('#finale-logo', { opacity: 0, y: 30, scale: .94, filter:
'blur(14px)' },
            { opacity: 1, y: 0, scale: 1, filter: 'blur(0px)', duration: dur,
ease: 'power2.out' })
    .fromTo('#finale-sub', { opacity: 0, y: 10 }, { opacity: 1, y: 0,
duration: dur * .6 }, dur * .4);
}
```

The logo starts building up while the camera is still pulling back, so the last second of the return and the title are one move. "Start again" fades the title out and brings the floor picker back on the same frame, with no reload.

CHAPTER 11

# PHONES

## WHERE MOST BUYERS WILL OPEN IT

- The panel moves to the bottom of the screen, 16 px from each side, and the floors keep the full height above it.
- There is no hover on a phone: the first tap on a floor selects it and lights it up, the "Enter" button flies in. Never fly on the first tap.
- For a vertical screen, generate a vertical version of the tower frame and of the flight (9:16) and trace the floors again. Cropping the horizontal video to a phone loses half the tower.
- Every pill is at least 44 × 44 points, the minimum Apple uses for anything you touch.
- All videos `muted playsinline`, or iPhone opens them full screen and the experience is gone.

```
@media (max-width: 760px) {
  .panel { top:auto; bottom:16px; right:16px; left:16px; width:auto;
transform:none; padding:22px; }
  .panel h1 { font-size: 30px; }
  .level .num { font-size: 52px; }
}
```

CHAPTER 12

# ONLINE AND DELIVERED

## AND WHAT TO CHARGE FOR IT

### PUBLISH

The whole experience is one `index.html` and an `assets` folder, so any static host works. On Vercel: drag the folder in, or push it to a GitHub repository and import it. Before the launch, send the developer a private link with `<meta name="robots" content="noindex">`, and remove it when they go public.

### CONNECT IT TO SALES

"Register interest" opens a short form with the chosen building, floor and unit already filled in, so the sales team knows what the buyer looked at before calling. Pass them in the link:


```
$('register').addEventListener('click', () => {
  const q = new URLSearchParams({ tower: building?.id || 'a', level:
current.n, unit: chosen?.id || '' });
  location.href = '/register?' + q;     // or the developer's CRM form
});
```

### THE CHECK BEFORE YOU SEND IT

1. Every join plays without a jump, a flash or a stop, in both directions.
2. Every floor band sits on its floor on a 13" laptop, a 21:9 monitor and a phone.
3. Floor numbers, unit types, areas and views match the developer's price list, one by one.
4. Double clicks during a flight do nothing.
5. The loader reaches 100 % on 4G, and nothing plays before it does.
6. No text, logo or watermark in the videos that the developer did not give you.

### WHAT YOU ARE SELLING

The developer is not buying a website. They are buying the minute in which a buyer stops reading a price list and picks their own floor, and that minute happens in the sales office, on the broker's phone and in every ad that points to the link. Price it as part of the launch, next to the film and the renders, because it uses the same images.


omnya lab
YOUR TURN
NOW A BUYER
CAN WALK IN
You have the tower, the floors, the flight in and the way back, on one link that opens on a phone. Send it to the developer before the launch, and put it in every ad: that is where buyers stop reading a price list and pick their own floor.
WANT US TO BUILD IT FOR YOUR TOWER?
Write to us on omnyalab.com with the plans and the 3D you have
THE FIRST IMAGE IS FREE
omnyalab.com · Venice and Dubai